



# MONROE COUNTY ROAD COMMISSION

840 S. Telegraph Road Monroe, Michigan 48161 Phone: (734) 240 -5102 Fax: (734) 240 -5101

## CONSTRUCTION PROJECTS Week of August 12, 2019

### Ash Township

#### **Sweitzer – Sigler to Ready**

The Monroe County Drain Commission will continue with the closure on Sweitzer Road at the Little Swan Creek Drain for replacement of the culvert under the road. The closure is located between Sigler Road and Ready Road. The replacement should be completed by the end of August. This will be a total road closure at the culvert. Local residents, south of the culvert will be able to access their homes from the Indian Trail Road intersection and those north of the culvert will have to come and go from the Ready Road intersection.

### Ash / Exeter Townships

#### **Exeter Road – Sigler to Carleton West**

Exeter Road between Nolan Road and Scofield Carleton Road Culvert Replacement: Exeter Road at Little Swan Creek is completely closed to all traffic at the culvert. Those living north of the bridge will have to access their homes from Scofield-Carleton Road and those south of the bridge from Nolan Road. The signed detour route around the project is via Sigler Road, Maxwell Road and Carleton West Road. Exeter Road is expected to be opened back up to traffic in Mid-September.

### Bedford Township

#### **Lewiston Estates Subdivision off Lewis Avenue**

Work scheduled for the upcoming week on the Lewiston Estates Special Assessment District project includes driveway removals and the installation of driveway culverts and storm sewers on Ashland Drive, Birchwood Drive and Fir Drive. Access to residences within the subdivision will be maintained during construction; however, motorists are encouraged to use caution when traveling through the work zone. Work in the Lewiston Estates Subdivision is expected to last through late-September.

#### **Sterns Road from Jackman Road to US-24 (Telegraph Road)**

Gerken Paving is scheduled to overlay Sterns Road between Jackman Road and US-24 (Telegraph Road) during the first part of the week of August 12<sup>th</sup>, weather permitting. The hot mix asphalt resurfacing portion of this project is expected to take approximately three (3) days to complete. During the paving operation, two-way traffic will be maintained on Sterns Road with single lane closures and traffic regulators. Short-term delays should be expected when traveling through the work zone during working hours.

## **Exeter Township**

### **S.Stony Creek – Sumpter to Palmer**

Tenmile Creek is tentatively scheduled to begin trenching and pre-pulverization on S. Stony Creek Road between Sumpter and Palmer. Base stabilization will follow this process and paving should take place 1-2 weeks after the base stabilization is completed. Shoulder work will follow paving. The road will be closed to through traffic until paving is completed.

### **Palmer – Sumpter to Oakville Watz**

Tenmile Creek is tentatively scheduled to begin trenching and pre-pulverization on Palmer Road between Sumpter and Oakville Watz. Base stabilization will follow this process and paving should take place 1-2 weeks after the base stabilization is completed. Shoulder work will follow paving. The road will be closed to through traffic until paving is completed.

## **Monroe Township**

### **7th Street – Herr to US 24**

7<sup>th</sup> Street between Herr and US 24 is tentatively scheduled for a single chip seal during the week of August 12<sup>th</sup>. The roads are scheduled to be swept the following day. The roads will be closed to through traffic during construction. All work is weather permitting.

## **Summerfield Township**

### **Cortz Road – Between Summerfield and Wells**

The Monroe County Drain Commission will be closing Cortz Road at the Cortz Drain for replacement of the culvert under the road. The closure is located between Summerfield Road and Wells Road. The closure is expected to begin Wednesday, August 14, 2019 and should only take one (1) day to complete, weather permitting. This will be a total road closure at the culvert. Local residents west of the culvert will be able to access their homes from the Summerfield Road intersection and those east of the culvert will have to come and go from the Wells Road intersection. Due to the short duration of the closure and local nature of the traffic a detour will not be signed.